



Oslo

Sustainable stormwater management in Oslo

Yvona Holbein, Stormwater Coordinator
Inga Potter, Planning Advisor
Oslo Municipality, *Agency for planning and building services*
November 8th 2023, C40 UFN Webinar





Stormwater management in Oslo Municipality



What are our main challenges?



What legal framework do we have as a municipality to adapt?



How do we achieve the necessary results?

Challenges

- ▶ Degradation of vegetation: loss of permeable surfaces, biodiversity and carbon storage

- ▶ Damage: High peak runoff (speed and volume) causes damage from erosion, washout and flooding

- ▶ Pollution: More frequent extreme events drag particles and pollution out to the rivers and fjord and create more overflow events from sewage systems

Oslo

Foto: Nyebilder

Challenges

- ▶ Damage: High peak runoff (speed and volume) causes damage from erosion, washout and flooding



- ▶ Pollution: More frequent extreme events drag particles and pollution out to the rivers and fjord and create more overflow events from sewage systems



- ▶ Degradation of vegetation: loss of permeable surfaces, biodiversity and carbon storage





Legal framework

Laws, strategies and guidelines in
Norway and Oslo Municipality



National laws and guidelines



The Planning and Building Act

The Planning and Building Act provides a broad framework for regulation of planning and building activities in Norway



Technical Regulations (TEK 17)

Regulations with technical requirements for design and construction works on a building site



State planning guidelines

for also climate mitigation and adaptation in planning processes

The Municipal Masterplan

for Oslo Municipality

incl. adaptation and stormwater issues

- ▶ **Managing stormwater**
- ▶ **Protection against flood risks**
- ▶ Extended limits to new buildings along the waterways
- ▶ Protection of green spaces
- ▶ Re-use of building land, seeking land-neutrality
- ▶ Protecting trees
- ▶ Protecting farmland and forests etc.



Oslo



Oslo

Forslag til offentlig ettersyn
22.06.2023

Proposal

Planbeskrivelse

Kommuneplanens arealdel


Oslo mot 2040



En grønnere, varmere
og mer skapende by
med plass til alle




Public health



Green roofs and facades




Urban agriculture



Climate strategy



Tree planting



Biodiversity

Strategy for Stormwater Management in Oslo


Approved by City Council in 2014



Strategy Goals:

1. Meeting climate challenges and reducing damage and inconvenience to people, buildings, property and infrastructure
2. Safeguard the environment and ensures good ecological and chemical quality in all water bodies
3. Using stormwater as a resource in the urban environment

Action Plan for Stormwater Management Approved in City Council in 2019.



18 actions in 5 categories:

1. Knowledge


2. Flooding

3. Oslo city setting good examples

4. Cooperation


5. Information and guidance

Organizational Chart City of Oslo



Red rings = All the agencies involved in stormwater management cooperation, coordinating the actions of the Action Plan for Stormwater Management

Oslo's cooperation for stormwater management






Achieving results? The Stormwater Guidebook

Comprehensive guidelines and
requirements for stormwater
management



The Stormwater Guidebook

“Requirements and Guidance for Stormwater Management in the City of Oslo”
Published September 2023



Konsentrasjonstiden for diffus strømming beregnes etter Kerbys formel:

$$8 \quad t_L = 1,44 \cdot \frac{(L \cdot N)^{0,467}}{S^{0,235}}$$

t_L : konsentrasjonstid diffus strømming (min)
 L : strømmingslengde for diffus strømming (m) NB: maks 350 m
 N : midlere retardasjonskoeffisient som hentes fra Tabell 7.2
 S : midlere helning (m/m) NB: maks helning 0,01

Merk at det ikke skal benyttes lengder over 350 meter i Kerbys formel, og at det anbefales at det benyttes lengder på maksimalt 100 meter (Chiu, 2013). Formelen er også begrenset til avrenningsfelt på under 4 hektar. For større tiltak kan det enten gjøres en inndeling i delneberfelter eller så kan avansert metode benyttes. Det bemerkes at ved store lengder for diffus strømming blir det komplekse avrenningsforhold og konsentrasjonstiden vil raskt kunne overstige 20 minutter. Dette vil utløse krav til å benytte avansert metode. Dette gjelder også når helning overstiger 0,01 m/m.


Konsentrasjonstiden for kanalisert strømming beregnes etter Kirpich' formel:

$$9 \quad t_K = 0,0195 \cdot \left(\frac{L^2 \cdot N}{S^{0,385}} \right)$$

t_K : konsentrasjonstid kanalisert strømming (min)
 L : strømmingslengde kanalisert strømming (m)
 S : midlere helning for kanalisert strømming (m/m)

I motsetning til Kerbys formel er det ikke angitt begrensninger i lengde i Kirpich' formel.

Retardasjonskoeffisient (N)
0,02
0,10
0,20
0,40
0,60
0,80




The Stormwater Guidebook


The guidebook includes:

- Detailed framework for management solutions (laws, guidelines etc.)
- Defines physical parameters that effect stormwater management, including city infrastructure and pollution
- Defines dimensioning and design criteria including future rainfall(**the 3-step approach**)
- Recommended application
- Solution catalogue

Traditional management of stormwater and waterways




Sustainable and climate-adapted management of stormwater and waterways



The 3-step stormwater approach

Oslo's dimensioning criteria


The 3-step approach strives to recreate the water cycle in a natural catchment by implementing nature based solutions for infiltration (step 1) retention (step 2) and safe flood paths (step 3).



Stormwater management: Who's responsible for the water?


Responsibility of the developer/owner
On-site management solutions primarily for low-moderate rain

City responsibility
City wide comprehensive systems for extreme rain



*possibly the developer where appropriate

A «stormwater management plan» must be delivered when planning a housing area



Step 1 (infiltration)

Light green = vegetation
 Yellow = extensive sedum roofs
 Dark green = raingarden

Step 2 (retention)

Dark green = raingarden

Step 3 (floodway)

Blue arrows, runoff direction



Step 1 Infiltration 10 mm




Step 1

Requirements should:

- Facilitate ecosystem services and multi-use blue-green areas
- Contribute to a natural water balance, including appropriate groundwater levels
- Improve and/or protect water quality in watercourses
- Reduce the amount of clean stormwater that reaches wastewater treatment plants
- Reduce drinking water consumption and associated energy use through rainwater reuse




Oslo




Step 1 Requirements Infiltration

- ▶ Step 1: the runoff from the building site in the event of a 10 mm rainfall must infiltrate into a permeable surfaces and have sufficient space in underlying soil ("shallow infiltration").
- ▶ A quantity requirement: minimum proportion of permeable surfaces
- ▶ A feature requirement: runoff from dense surfaces must run into the stretching scope of permeable surfaces
- ▶ 10 mm ensures that 95-99% of the annual precipitation has the opportunity to infiltrate and maintains simultaneous runoff from "**first flush**" which contains the majority of pollution.
- ▶ "Exemptions" for areas where runoff is collected and reused



Blue Green Index



Blue Green




Normområder

- Åpen by
- Tett by og kollektivknutepunkt




	Geographical location	Blue and green factor
Land use		
Open residential area (small houses)	City	1,0
Other residential area (block)	Dense city	0,8
	Open city	0,9
School, kindergarten and health institution	Dense city	0,7
	Open city	0,8
Culture and sport	Dense city	0,6
	Open city	0,8
Office and commercial	Dense city	0,5
	Open city	0,6
Mixed use	Dense city	Main land use
	Open city	Main land use
Industry, storage and logistic	City	0,4
Public space		
Street	Dense city	0,10
	Open city	0,15
Pedestrian street	City	0,3
Square	City	0,4
Green square	City	0,8

Blue Green Index



Oslo						BLÅGRØNN FAKTOR OSLO			
Prosjekttittel	Gateadresse	Tomteareal m ²	Dato						
Fyll inn	Fyll inn	0	Dag	Måned	År				
Tiltak	Beskrivelse								
STYRKET BLÅGRØNN STRUKTUR OG BIOLOGISK MANGFOLD			Stykk	Verdi pr stk					
	Blågrønn struktur	Fysisk utvidelse av eksisterende blågrønn struktur	0	0,05	0,00				
		Restaurering eller etablering av nye leveområder for biologisk mangfold	0		0,00				
		Gjenåpning av lukkede vassdrag (bekker og elver i rør)	0		0,00				
		Samordning av tiltak med tilgrensende områder og/eller eiere av nabogrunn	0		0,00				
		Oppsamling av overvann for vanning og annen gjenbruk	0		0,00				
TERRENG OG FLATER			Areal m ²	Verdi pr m ²					
	Grønt terreng	Eksisterende felt- og busksjikt inntil to meters høyde (urbant landbruk og vegetert mark)	0	1,4	0,00				
		Nytt felt- og busksjikt inntil to meters høyde (urbant landbruk og vegetert mark)	0	1,2	0,00				
		Eksisterende bunnsjikt som plen, sedum, mose og lav	0	1,0	0,00				
		Nytt bunnsjikt som plen, sedum, mose og lav	0	0,8	0,00				
	Grønt tak	Dybde vekstmedium ≥ 80 cm	0	0,9	0,00				
		Dybde vekstmedium 40–80 cm	0	0,7	0,00				
		Dybde vekstmedium 10–39 cm	0	0,5	0,00				
		Dybde vekstmedium 3–9 cm	0	0,3	0,00				
	Grønn vegg	Plantevegg og vertikalt urbant landbruk	0	0,6	0,00				
		Slyng- og klatreplanter	0	0,3	0,00				
	Regnbed, vannspeil og våtmark	Regnbed er frodige og variert beplantede fordypninger for oppsamling og infiltrering av overvann. Vannspeil (elv, bekk, dam) skal ha bunnsstrat og kantvegetasjon. Våtmark er fuktig mark som er overfløttet eller har vann nær overflaten store deler av året.	0	3	0,00				
	Terrengforsenkning og vadi	Terrengforsenkning er en fordypning i terreng eller flate, i form av vegetert overflate, lekeplass, torg og lignende, som er opparbeidet for uteopphold, der overvann kan fordroyes og infiltreres gjennom permeabel overflate. Vadier er grønne grøfter, eventuelt beplantede, og de er velegnet for oppsamling og bortledning av overvann.	0	1	0,00				
	Delvis åpen flate	Permeable grønne overflater (gressarmert dekke)	0	0,4	0,00				
		Semi-permeabel grå flate (sand, grus, singel, pukk og gjennomhullede faste dekker)	0	0,3	0,00				
		Delvis permeabel grå flate (gatestein satt i pukk og lignende på permeabel undergrunn)	0	0,2	0,00				
	Tett flate	Tette flater der regnvann ledes til blågrønt tiltak på tomten med infiltrasjons- og fordryningskapasitet etter krav til overvannshåndtering (dokumentasjonsbehov) eller til vannoppsamler	0	0,1	0,00				
TRÆR			Stykk	Verdi pr stk					
	Eksisterende trær	Svært store trær – stammeomkrets over 200 cm	0	70	0,00				
		Store trær – stammeomkrets 90–200 cm	0	50	0,00				
		Små trær – stammeomkrets under 90 cm	0	40	0,00				
	Nye trær	Store trær – fremtidig høyde over 10 meter	0	30	0,00				
		Små trær – fremtidig høyde under 10 meter	0	20	0,00				
Utarbeidet av Plan- og bygningssetaten. Høringsversjon 06.04.2022				BLÅGRØNN FAKTOR	0,00				

Step 2 Retain climate adjusted 5-year rain





Step 2 Goals/Requirements



- ▶ Reduce the risk of stormwater damage and improve land use
- ▶ Minimize pollution of watercourses by sedimentation, and reducing overflow from wastewater systems
- ▶ Reduce the amount of clean water being sent to wastewater treatment plants, improve the quality of the sewage sludge, and reduce energy costs in the sewage system
- ▶ Requirements should stimulate local nature based and/or multifunctional retention solutions
- ▶ Requirements must be possible to document so that we know that we are achieving the desired result

Step 2 Design


- ▶ Dimensioning criteria have been lowered from a climate adjusted 20-year return period to 5-year, to stimulate for more open land based retention
- ▶ Clearer definition of design parameters including runoff coefficients, controlled discharge possibilities (including municipal pipes and surface runoff).
- ▶ Clearer definition of infiltration that allows for some infiltration, without it being the only discharge



Introducing the term “shallow infiltration” for step 1 and “deep infiltration” for step 2

Only suitable for “Shallow infiltration” (top 0.5 m)


Possibility of deep infiltration



Why?

Previously “local management” was interpreted as the infiltration of all water up to a climate adjusted 20-year rainfall. This was almost impossible to document or achieve as Oslo is primarily on marine clay.

Unsuitable for deep or shallow infiltration




Step 2
Defining parameters

Velg kartlag ✕

Grunnforhold som er delvis kartlagt

- Borepunkter hvor leire er påvist [Mer info](#)
 - Leire
- Borepunkter hvor kvikkleire er påvist [Mer info](#)
 - Kvikkleire påvist
 - Kvikkleire tolket
- Kvikkleiresoner fra NVE [Mer info](#)
 - faregrad, løse- og utlopsområder
 - Høy (løsneområde)
 - Høy (utlopsområde)
 - Middels (løsneområde)
 - Middels (utlopsområde)
 - Lav (løsneområde)
 - Lav (utlopsområde)
 - Ingen
- Historiske kart [Mer info](#)
- Informasjon om hvordan bygninger er fundamentert [Mer info](#)

Ground conditions* shows a lot of clay (blue and red)



Step 2
Defining parameters

- Observasjoner av fjell i dagen [Mer info](#)
- Dybde til antatt berg [Mer info](#)
- Risiko for setninger [Mer info](#)
- Marinn grense [Mer info](#)

Step 2

Defining parameters

For building sites within 250 m of a river/fjord, retention is not necessary given that water quality is acceptable, and discharge does not lead to erosion or other damage. Step 1 must still be fulfilled.



Step 3


Secure 100-year climate adjusted rain




Step 3

Goals/Requirements

- ▶ Reduce the risk of damage from stormwater locally and downstream of the building area
- ▶ Allocate space for floodways (runoff from the property during a future 100-year rain)
- ▶ Entry and outlet points through the building site should not be changed. The floodways must guide water towards the primary floodway system (unless a better solution has been selected and approved by the city).
- ▶ Where there is also a floodway traverse the building site, space must be set aside for runoff from upstream as well as on-site runoff





Example



New flood modelling– from runoff-lines to depth and speed

Step 3

Comprehensive planning






Mike + (Mike Flood)



Step 3


Floodway design in roads



Step 3

Comprehensive planning

- Temakart**
- Grunnforhold - kvikkleire
 - Skred i bratt terreng [Mer info](#)
 - Vannveier [Mer info](#)
 - Flom i elver og bekker
 - Overvann [Mer info](#)
 - Modellert vanndybde (D) [Mer info](#)
 - Modellert dybdeintegret hastighet (DV) [Mer info](#)
 - Avrenningsmønster [Mer info](#)
 - Avrenningslinjer (Dreneringslinjer) [Mer info](#)
 - Overvannsrør med direkte utløp til sjø og vassdrag [Mer info](#)
 - Luftsonkart [Mer info](#)




Step 3

Comprehensive planning

Temakart

- Grunnforhold - kvikkleire
- Skred i bratt terreng [Mer info](#)
- Vannveier [Mer info](#)
- Flom i elver og bekker
- Overvann [Mer info](#)
- Modellert vanndybde (D) [Mer info](#)
- Modellert dybdeintegret hastighet (DV) [Mer info](#)
- Avrenningsmønster [Mer info](#)
- Avrenningslinjer (Dreneringslinjer) [Mer info](#)
- Overvannsrør med direkte utløp til sjø og vassdrag [Mer info](#)
- Luftsonkart [Mer info](#)



Detaljer

Achieving our goals: Implications of the new guidebook



Specific requirements for Step 1

More permeable surfaces that hold back precipitation via interception, evapotranspiration and infiltration, dampen flood peaks and water



Down scaled requirements for Step 2 with increased focus on open solutions

Multifunctional outdoor spaces/increased utility, robust solutions that are accessible and that provide increased opportunities for maintenance, adaptation to needs and operational experience



Requirement for Step 3 uphold and secure existing runoff pattern

Diversion of water prevents damage as well as helps maintain natural waterways and runoff patterns



Oslo

Contact:

Inga Potter

inga.potter@pbe.oslo.kommune.no

Planning Advisor Stormwater Management

Yvona Holbein

yvona.holbein@pbe.oslo.kommune.no

Coordinator for Stormwater Management,

Agency for Planning and Building Services (PBE),
Oslo Municipality, Norway

